B I D P R O P O S A L

SPECIFICATION NO. PW22-0395F

S YAKIMA AVENUE SIDEWALK

(S 67th to S 70th)

&

BIRNEY ELEMENTARY SRTS IMPROVEMENTS

(S 76th)

The undersigned hereby certifies that he/she has examined the location and construction details of work as outlined on the Plans and Specifications for Project Nos. PWK-G0055 / TIB Project No. P-P-128(P07)-1 & PWK-00802-04-01, and has read and thoroughly understands the Plans and Specifications and contract governing the work embraced in this improvement and the method by which payment will be made for said work, and hereby proposes to undertake and complete the work embraced in this improvement in accordance with said Plans, Specifications and contract and at the following schedule of rates and prices.

NOTE:

1. Unit prices of all items, all extensions and total amount of bid should be shown. Show unit prices in figures only.
2. The notations below the item numbers refer to the specification section where information may be found regarding each contract item. These notations are intended only as a guide and are not warranted to refer to all specification sections where information may be found.
3. The base bid will be determined by adding the total of Schedule A and Schedule B.

All bid items are sorted in the following schedules:

- **Schedule A: Project Bid Items _ S YAKIMA AVENUE SIDEWALK (S 67th to S 70th)**
- **Schedule B: Project Bid Items _ BIRNEY ELEMENTARY SRTS IMPROVEMENTS (S 76th)**

			Schedule A		Schedule B	
			S YAKIMA AVENUE SIDEWALK (S 67th to S 70th)		BIRNEY ELEMENTARY SRTS IMPROVEMENTS (S 76th)	
ITEM NO./ SPEC	ITEM DESCRIPTION	Cost/Unit	Total Qnty.	Total Cost	Total Qnty.	Total Cost
R1 1-09	Mobilization	$_____ Lump Sum	50% Lump Sum	$_____	50% Lump Sum	$_____
R2 1-10	Pedestrian Traffic Control	$_____ Lump Sum	50% Lump Sum	$_____	50% Lump Sum	$_____
R3 1-10	Project Temporary Traffic Control	$_____ Lump Sum	50% Lump Sum	$_____	50% Lump Sum	$_____
R4 2-01	Clearing and Grubbing	$_____ Lump Sum	50% Lump Sum	$_____	50% Lump Sum	$_____
R5 2-02	Removal of Structures and Obstructions	$_____ Lump Sum	50% Lump Sum	$_____	50% Lump Sum	$_____
R6 2-02	Existing Irrigation Systems	$ 2000.00 Force Account	50% FA	$ 1000.00	50% FA	$ 1000.00
R7 2-03	Subgrade Maintenance and Protection Plan	$_____ Lump Sum	50% Lump Sum	$_____	50% Lump Sum	$_____
R8 2-03	Roadway Excavation, Incl. Haul	$_____ Cu. Yd.	23	$_____	30	$_____
R9 2-09	Shoring or Extra Excavation Class B	$_____ Sq. Ft.	248	$_____	184	$_____
R10 2-09	Structure Excavation Class B	$_____ Cu. Yd.	17	$_____	12	$_____
R11 2-14	Remove Existing Pavement, Type I, Class A4	$_____ Sq. Yd.	191	$_____	188	$_____
R12 2-14	Remove Existing Pavement, Type I, Class C6	$_____ Sq. Yd.	70	$_____	68	$_____
R13 2-15	Remove Curb	$_____ Lin. Ft.	225	$_____	177	$_____
R14 2-16	Remove Catch Basin	$_____ Each	4	$_____	2	$_____

Contractor's Name: _____

			Schedule A		Schedule B	
			S YAKIMA AVENUE SIDEWALK (S 67th to S 70th)		BIRNEY ELEMENTARY SRTS IMPROVEMENTS (S 76th)	
ITEM NO./ SPEC	ITEM DESCRIPTION	Cost/Unit	Total Qnty.	Total Cost	Total Qnty.	Total Cost
R15 4-04	Crushed Surfacing Top Course	$_____ Ton	5	$_____	13	$_____
R16 5-04	HMA CL 1/2" PG 58H-22 for Temporary Pavement Patch	$_____ Ton	5	$_____	4	$_____
R17 5-04	HMA for Approach CL 1/2" PG 58H-22	$_____ Sq. Yd.	0	$ 0.00	57	$_____
R18 7-02	HMA CL 1/2" PG 58H-22	$_____ Ton	17	$_____	15	$_____
R19 7-05	Catch Basin Type 2	$_____ Each	1	$_____	1	$_____
R20 7-05	Catch Basin Type 1	$_____ Each	3	$_____	2	$_____
R21 7-05	Reconnect Existing Sewer Pipe to New Structure	$_____ Each	3	$_____	4	$_____
R22 7-08	CDF for Pipe Abandonment	$_____ Cu. Yd.	1	$_____	0	$ 0.00
R23 7-08	Plugging Existing Pipe	$_____ Each	2	$_____	0	$ 0.00
R24 7-17	Removal and Replacement of Unsuitable Material Incl. Haul	$_____ Cu. Yd.	9	$_____	6	$_____
R25 7-17	Ductile Iron Storm Sewer Pipe 12 In. Diam.	$_____ Lin. Ft.	31	$_____	0	$ 0.00
R26 7-17	PVC Storm Sewer Pipe 12 In. Diam.	$_____ Lin. Ft.	0	$ 0.00	25	$_____
R27 7-17	Testing Sewer Pipe	$_____ Lin. Ft.	31	$_____	25	$_____

Contractor's Name: _____

			Schedule A		Schedule B	
			S YAKIMA AVENUE SIDEWALK (S 67th to S 70th)		BIRNEY ELEMENTARY SRTS IMPROVEMENTS (S 76th)	
ITEM NO./ SPEC	**ITEM DESCRIPTION**	**Cost/Unit**	**Total Qnty.**	**Total Cost**	**Total Qnty.**	**Total Cost**
R28 8-01	Erosion/Water Pollution Control	$_____ Lump Sum	50% Lump Sum	$_____	50% Lump Sum	$_____
R29 8-01	Stormwater Pollution Prevention Plan (SWPPP)	$_____ Lump Sum	50% Lump Sum	$_____	50% Lump Sum	$_____
R30 8-02	Site Restoration	$_____ Lump Sum	50% Lump Sum	$_____	50% Lump Sum	$_____
R31 8-04	Cement Conc. Traffic Curb and Gutter	$_____ Lin. Ft.	315	$_____	277	$_____
R32 8-06	Cement Conc. Driveway Entrance	$_____ Sq. Yd.	13	$_____	0	$ 0.00
R33 8-14	Cement Conc. Sidewalk	$_____ Sq. Yd.	46	$_____	123	$_____
R34 8-14	Pedestrian Curb	$_____ Lin. Ft.	85	$_____	147	$_____
R35 8-14	Cement Conc. Curb Ramp	$_____ Each	8	$_____	8	$_____
R36 8-14	Residential Storm Drain Through Curb	$_____ Each	1	$_____	0	$ 0.00
R37 8-21	Permanent Signing	$_____ Lump Sum	67% Lump Sum	$_____	33% Lump Sum	$_____
R38 8-22	Plastic Stop Line	$_____ Lin. Ft.	22	$_____	22	$_____
R39 8-22	Plastic Crosswalk	$_____ Lin. Ft.	310	$_____	290	$_____
R40 8-20	Pedestrian Activated Crosswalk Beacon System, Complete, S Yakima Ave & S 68th St	$_____ Each	1	$_____	1	$_____
Total Base Bid Subtotals (Not Including Sales Tax)				$_____		$_____

Contractor's Name: _____

Summary

Schedule	Total Construction Cost (Not Including Sales Tax)
Schedule A: Total Construction Cost **S YAKIMA AVENUE SIDEWALK (S 67th to S 70th)**	$ _____
Schedule B: Total Construction Cost **BIRNEY ELEMENTARY SRTS IMPROVEMENTS (S 76th)**	$ _____
GRAND TOTAL (Schedule A + Schedule B)	$ _____

Proposal for Incorporating Recycled Materials into the Project

In compliance with a new law that went into effect January 1, 2016 (SHB1695), the Bidder shall propose below, the total percent of construction aggregate and concrete materials to be incorporated into the Project that are recycled materials. Calculated percentages must be within the amounts allowed in Section 9 03.21(1)E, Table on Maximum Allowable Percent (By Weight) of Recycled Material, of the Standard Specifications.

Proposed total percentage: _____ percent (%)

Note: Use of recycled materials is highly encouraged within the limits shown above, but does not constitute a Bidder Preference, and will not affect the determination of award, unless two or more lowest responsive Bid totals are exactly equal, in which case proposed recycling percentages will be used as a tie-breaker, per the APWA GSP in Section 1-02.6 of the Special Provisions. Regardless, the Bidder's stated proposed percentages will become a goal the Contractor should do its best to accomplish. Bidders will be required to report on recycled materials actually incorporated into the Project, in accordance with the APWA GSP in Section 1 06.6 of the Special Provisions.

Bidder: _____

Signature of Authorized Official: _____

Date: _____